



**SALEM**  
engineering group, inc.

---

## **GEOTECHNICAL ENGINEERING INVESTIGATION**

**PROPOSED STORAGE BUILDINGS  
NEAR THE SOUTHEAST CORNER OF SCHNOOR STREET  
AND MODOC STREET  
(LAT 36.9500025, LONG -120.082137)  
MADERA, CALIFORNIA**

**SALEM PROJECT NO. 1-221-0369  
APRIL 28, 2021**

***PREPARED FOR:***

**MS. ERIN VOLPP  
WHSE PARTNERS  
C/O DBKO DESIGN+BUILD  
1187 N. WILLOW AVENUE, SUITE 103 #667  
CLOVIS, CALIFORNIA 93611**

***PREPARED BY:***

**SALEM ENGINEERING GROUP, INC.  
4729 W. JACQUELYN AVENUE  
FRESNO, CA 93722  
P: (559) 271-9700  
F: (559) 275-0827  
[www.salem.net](http://www.salem.net)**



4729 W. Jacquelyn Avenue  
Fresno, CA 93722  
Phone (559) 271-9700  
Fax (559) 393-9710

April 28, 2021

Project No. 1-221-0369

Ms. Erin Volpp

**WHSE Partners**

c/o DBKO DESIGN+BUILD

1187 N. Willow Avenue, Suite 103 #667

Clovis, California 93611

**Subject: GEOTECHNICAL ENGINEERING INVESTIGATION  
PROPOSED STORAGE BUILDINGS  
NEAR THE SOUTHEAST CORNER OF SCHNOOR STREET AND MODOC STREET  
(LAT 36.9500025, LONG -120.082137)  
MADERA, CALIFORNIA**

Dear Ms. Volpp:

With your request and authorization, SALEM Engineering Group, Inc. (SALEM) has prepared this geotechnical engineering investigation report for the proposed storage buildings to be located at the subject site in Madera, California.

The accompanying report presents our findings, conclusions, and recommendations regarding the geotechnical aspects of designing and constructing the project as presently proposed. In our opinion, the proposed project is feasible from a geotechnical viewpoint provided our recommendations are incorporated into the design and construction of the project.

We appreciate the opportunity to assist you with this project. Should you have questions regarding this report or need additional information, please contact the undersigned at (559) 271-9700.

Respectfully Submitted,

**SALEM ENGINEERING GROUP, INC.**

A handwritten signature in blue ink that reads 'Ahmad Dalqamouni'.

Ahmad Dalqamouni, Ph.D, M.CE  
Geotechnical Project Engineer  
Central / Northern California

A handwritten signature in blue ink that reads 'Dean B. Ledgerwood II'.

Dean B. Ledgerwood II, EIT, PG, CEG  
Geotechnical Manager  
PG 8725 / CEG 2613

## TABLE OF CONTENTS

1. PURPOSE AND SCOPE .....	1
2. SITE LOCATION AND DESCRIPTION .....	1
3. PROJECT DESCRIPTION .....	1
4. FIELD EXPLORATION .....	2
5. LABORATORY TESTING .....	3
6. SOIL AND GROUNDWATER CONDITIONS .....	3
6.1. Subsurface Conditions .....	3
6.2. Groundwater.....	4
6.3. Soil Corrosion Screening .....	4
6.4. Results of Percolation Testing .....	4
7. GEOLOGIC SETTING.....	5
8. GEOLOGIC HAZARDS .....	5
8.1. Faulting and Seismicity.....	5
8.2. Surface Fault Rupture .....	6
8.3. Ground Shaking .....	6
8.4. Liquefaction .....	6
8.5. Lateral Spreading .....	7
8.6. Landslides .....	7
8.7. Tsunamis and Seiches .....	7
9. CONCLUSIONS AND RECOMMENDATIONS .....	7
9.1. General Conclusions .....	7
9.2. Surface Drainage and Storm Water Basin Design and Maintenance .....	8
9.3. Site Grading .....	9
9.4. Soil and Excavation Characteristics.....	11
9.5. Materials for Fill .....	12
9.6. Seismic Design Criteria .....	13
9.7. Shallow Foundations.....	14
9.8. Interior Concrete Slabs-on-Grade .....	15
9.9. Exterior Slabs on Grade .....	16
9.10. Lateral Earth Pressures and Frictional Resistance .....	17
9.11. Temporary Excavations .....	18
9.12. Underground Utilities .....	19
9.13. Pavement Design .....	19
10. PLAN REVIEW, CONSTRUCTION OBSERVATION AND TESTING .....	20
10.1. Plan and Specification Review.....	20
10.2. Construction Observation and Testing Services .....	21
11. LIMITATIONS AND CHANGED CONDITIONS .....	21

## **TABLE OF CONTENTS (cont.)**

### **FIGURES**

Figure 1, Vicinity Map

Figure 2, Site Plan

### **APPENDIX A – FIELD INVESTIGATION**

Figure A1 and A10, Logs of Exploratory Soil Borings B-1 through P-1

### **APPENDIX B – LABORATORY TESTING**

Consolidation Test Result

Direct Shear Test Result

Gradation Curves

Atterberg Limits Test Result

Expansion Index Test Result

Resistance Value Test Result

Corrosivity Test Results

Soil Resistivity Test Result

---

**GEOTECHNICAL ENGINEERING INVESTIGATION  
PROPOSED STORAGE BUILDINGS  
SOUTHEAST CORNER OF SCHNOOR STREET & MODOC STREET  
MADERA, CALIFORNIA**

**1. PURPOSE AND SCOPE**

This report presents the results of our geotechnical engineering investigation for the proposed storage buildings to be located 600 feet southeast of the intersection of S. Schnoor Street and Modoc Street, (Coordinates: 36.9500025, -120.082137) in Madera, California, as depicted on Figure 1, Vicinity Map.

SALEM Engineering Group, Inc. (SALEM) has completed this geotechnical engineering investigation with the purpose to observe and sample the subsurface conditions encountered at the site and provide conclusions and recommendations relative to the geotechnical aspects of constructing the project as presently proposed. The recommendations presented herein are based on analysis of the data obtained during the investigation and our local experience with similar soil and geologic conditions.

If project details vary significantly from those described herein, SALEM should be contacted to determine the necessity for review and possible revision of this report.

**2. SITE LOCATION AND DESCRIPTION**

The subject site is located approximately 600 feet south of the intersection of S. Schnoor Street and Modoc Street, (Coordinates: 36.9500025, -120.082137), and immediately across from intersection of W. Industrial Ave and S. Schnoor Street in Madera, California (see Vicinity Map, Figure 1). At the time of our field reconnaissance, the area of the project site was vacant land. Based on google historic imagery database, no indications if the project site has been used for farming or commercial use in the past 25 years. The developed parcels surrounding the site is generally has been used for residential and commercial/light industrial uses.

The site was observed to be bounded by vacant land to the south, vacant land and commercial/ residential development to the north, S. Schnoor Street and commercial properties to the west, and vacant commercial land to the east. The vicinity surrounding the subject site includes commercial, industrial, and residential single family residences.

The project site area is relatively flat with elevations of about 262 feet above mean sea level (AMSL), based on Google Earth Imagery.

**3. PROJECT DESCRIPTION**

Based on information provided by Mr. Flores and site plan dated April 7 2021 (Drawing by DBKO Design and Build Job # 21107), it is our understanding the project will include four (4) storage unit buildings, with plan view areas ranging from 35,100 square feet to 37,050 square feet.

It is anticipated the proposed construction will comprise of wood or metal framing supported on shallow spread foundations with concrete slabs on grade. Structural loads were not provided to us at the time this proposal was prepared. Based on our experience with similar projects maximum column and wall bearing loads of about 15 to 20 kips and 1 to 3 kips per foot, respectively, are anticipated. Floor slab soil bearing pressure is expected not to exceed 150 psf.

Appurtenant construction is known to consist of Portland cement concrete paving, underground utilities, and isolated landscape areas. A site grading plan was not available at the time of preparation of this report.

In addition, a ponding basin is planned north of the area of the proposed storage buildings.

Based on the relatively flat grade at the project site during our field exploration, it is anticipated that cuts and fills during earthwork will be on the order of 1 to 2 feet to providing a level area and positive site drainage for the project area. In the event that changes occur in the nature or design of the project, the conclusions and recommendations contained in this report will not be considered valid unless the changes are reviewed, and the conclusions of our report are modified.

The site location and approximate locations of proposed improvements are shown on the Site Plan, Figure 2.

## **4. FIELD EXPLORATION**

### **4.1. Drilled Test Bores**

Our field exploration consisted of site surface reconnaissance and subsurface exploration. On April 15, 2021, a total of Ten (10) exploratory test borings (B-1 and B-10) were drilled to depths ranging from 15 to 35.0 feet below site grade. The test borings were drilled within or near the proposed building areas at the approximate locations shown on Figure No. 2, Site Plan. The test borings were advanced with 6 5/8-inch hollow-stem auger rotated by a truck-mounted CME-45C drill rig.

The materials encountered in the test borings were visually classified in the field, and logs were recorded by a field engineer at that time. Visual classification of the materials encountered in the test borings was generally made in accordance with the Unified Soil Classification System (ASTM D2487).

A Unified Soil Classification Chart and key to sampling is presented in Appendix A, including the test boring logs. Subsurface soil samples were obtained by driving a Modified California sampler (MCS) or a Standard Penetration Test (SPT) sampler. The Boring Logs include the soil type, color, moisture content, dry density, and the applicable Unified Soil Classification System symbol. The location of the test borings were determined by measuring from site features determined from information provided to us. Hence, accuracy can be implied only to the degree that this method warrants. The actual boundaries between different soil types may be gradual and soil conditions may vary. For a more detailed description of the materials encountered, the Boring Logs in Appendix A should be consulted.

Penetration resistance blow counts were obtained by dropping a 140-pound automated trip hammer through a 30-inch free fall to drive the sampler to a maximum penetration of 18 inches. The number of blows required to drive the last 12 inches, or less if very dense or hard, is recorded as Penetration Resistance (blows/foot) on the logs of borings.

Soil samples were obtained from the test borings at the depths shown on the test boring logs. The MCS samples were recovered and capped at both ends to preserve the samples at their natural moisture content; SPT samples were recovered and placed in a sealed bag to preserve their natural moisture content. At the

completion of drilling and sampling, the test borings were backfilled with drill cuttings. Consequently, some settlement should be anticipated.

#### **4.2. Percolation Testing**

As requested, one (1) percolation tests was performed within the planned ponding basin at a depth of approximately 8 feet below site grade. It is our understanding that the results of the testing performed will be utilized by others for the proposed infiltration basin design.

The percolation test was conducted using an approximately 6-inch diameter percolation borehole using hollow stem auger. Approximately 2 inches of gravel was placed in the bottom of the hole followed by a 3-inch diameter perforated pipe. The holes were pre-saturated prior to percolation testing. The findings of the percolation testing is summarized in Section 6.4 of this report. The approximate locations of the percolation tests performed are shown on Figure 2 included at the end of this report.

### **5. LABORATORY TESTING**

Laboratory tests were performed on selected soil samples to evaluate their physical characteristics and engineering properties. The laboratory-testing program was formulated with emphasis on the evaluation of natural moisture, density, shear strength, gradation, expansion index, plasticity index, and soil resistivity of the materials encountered.

In addition, chemical tests were performed to evaluate the corrosivity of the soils to buried concrete and metal. Details of the laboratory test program and the results of laboratory test are summarized in Appendix B. This information, along with the field observations, was used to prepare the final boring logs in Appendix A.

### **6. SOIL AND GROUNDWATER CONDITIONS**

#### **6.1. Subsurface Conditions**

The subsurface conditions encountered appear typical of those found in the geologic region of the site. In general, the soils encountered predominantly consisted of firm to stiff sandy silty clay, underlain by medium dense sandy silt, clayey silty sand, and poorly graded sand with silt, to the maximum depth explored of 35 feet below site grade. Cemented soil that is locally called Hardpan, was encountered at various depths between 8 feet and 16 feet below site grade.

Two direct shear tests resulted in an internal angle of friction of 39 and 43 degrees with a cohesion values of 153 and 61 pounds per feet, respectively. An expansion index test performed on a near surface soil sample resulted in an expansion index of 20. Three (3) Atterberg limits tests performed on selected soil samples resulted in plasticity indexes of 4, 3 and 8, with liquid limits of 22, 26, and 23, respectively.

R-value testing performed on shallow depth sample resulted in an R-Value of 63

The soils were classified in the field during the drilling and sampling operations. The stratification lines were approximated by the field engineer on the basis of observations made at the time of drilling. The actual boundaries between different soil types may be gradual and soil conditions may vary. For a more detailed description of the materials encountered, the Boring Logs in Appendix A should be consulted.

## 6.2. Groundwater

The test boring locations were checked for the presence of groundwater during and after the drilling operations. Free groundwater was not encountered during this investigation. Available groundwater depth records with the Department of Water Resources ([www.wdl.water.ca.gov/WaterDataLibrary](http://www.wdl.water.ca.gov/WaterDataLibrary)) indicate, Local Well No. 369518N1200777W001 located approximately 0.35 miles northeast of the project site reported historical high groundwater depth of 19.2 feet below ground surface in May 1945.

It should be recognized that water table elevations may fluctuate with time, being dependent upon seasonal precipitation, irrigation, land use, localized pumping, and climatic conditions as well as other factors. Therefore, water level observations at the time of the field investigation may vary from those encountered during the construction phase of the project. The evaluation of such factors is beyond the scope of this report.

## 6.3. Soil Corrosion Screening

Excessive sulfate in either the soil or native water may result in an adverse reaction between the cement in concrete and the soil. The 2019 Edition of ACI 318 (ACI 318) has established criteria for evaluation of sulfate and chloride levels and how they relate to cement reactivity with soil and/or water. A soil sample was obtained from the project site and was tested for the evaluation of the potential for concrete deterioration or steel corrosion due to attack by soil-borne soluble salts and soluble chloride. The water-soluble sulfate concentration in the saturation extract from the soil sample was detected to be less than 50 mg/kg.

ACI 318 Tables 19.3.1.1 and 19.3.2.1 outline exposure categories, classes, and concrete requirements by exposure class. ACI 318 requirements for site concrete based upon soluble sulfate are summarized in Table 6.3 below.

**TABLE 6.3**  
**WATER SOLUBLE SULFATE EXPOSURE REQUIREMENTS**

<b>Dissolved Sulfate (SO<sub>4</sub>) in Soil % by Weight</b>	<b>Exposure Severity</b>	<b>Exposure Class</b>	<b>Maximum w/cm Ratio</b>	<b>Minimum Concrete Compressive Strength</b>	<b>Cementitious Materials Type</b>
0.005	Negligible	S0	N/A	2,500 psi	No Restrictions

The water-soluble chloride concentration detected in saturation extract from the soil sample was 27 mg/kg. In addition, testing performed on a near surface soil resulted in a minimum resistivity value of 6,882 ohm-centimeters. Based on the results, these soils would be considered to have a “moderately corrosive” potential to buried metal objects (per National Association of Corrosion Engineers, Corrosion Severity Ratings).

It is recommended that a qualified corrosion engineer be consulted regarding protection of buried steel or ductile iron piping and conduit or, at a minimum, applicable manufacturer’s recommendations for corrosion protection of buried metal pipe be closely followed. Additional corrosion testing for minimum resistivity may need to be performed if required by the pipe manufacturer.

## 6.4. Results of Percolation Testing

One (1) percolation test was performed near the areas of the proposed infiltration basin. Based on our communications with the client, the percolation testing for the infiltration area included one percolation tests at depths between 5 and 8 feet below site grade. The following table includes a summary of the percolation testing for the proposed basin infiltration system. It is our understanding that the findings of



the table below will be utilized by the designer to determine depth and sizing of the proposed infiltration basin system.

The approximate location of the percolation tests are shown on the attached Figure 2. Approximately 6-inch diameter percolation boreholes were advanced using a truck mounted drill rig. Approximately 2 inches of gravel was placed in the bottom of each hole followed by a 3-inch diameter perforated pipe. The annulus surrounding the perforated pipe was backfilled with gravel. The holes were pre-saturated before percolation testing commenced. The following table includes a summary of the test holes that produced percolation rates:

Location	Depth, BSG (feet)	Gravel Pack Corrected Unfactored Percolation Rate (minutes per inch)	Estimated Unfactored Infiltration Rate (inches/hour)
P-1	8.0	59.7	0.1

The results of the percolation testing indicate the materials tested have low infiltration characteristics. If considered feasible, the proposed basin may be designed based on an unfactored infiltration rate of about 0.1 inches per hour. The infiltration rate should be factored due to anticipated reduction due to silt accumulation and hardpan. At a minimum a factor of safety of 3 should be considered for design. Variations in soil type and soil density across the infiltration area of the system can influence the infiltration rate.

## 7. GEOLOGIC SETTING

The project site is in the Great Valley Geomorphic Province, which is a topographic and structural basin that is bounded on the east by the Sierra Nevada and on the west by the Coast Ranges. The Sierra Nevada, a fault block dipping gently southwestward, is made up of igneous and metamorphic rocks of pre-Tertiary age that comprise the basement complex beneath the Valley. The Coast Ranges contain folded and faulted sedimentary rocks of Mesozoic and Cenozoic age, which are similar to those rocks that underlie the Valley at depth and non-conformably overlie the basement complex; gently dipping to nearly horizontal sedimentary rocks of Tertiary and Quaternary age overlie the older rocks. The Great Valley Province is an alluvial plain, drained by the Sacramento River in the north and the San Joaquin Valley in the south, each join and flow out the San Francisco Bay. The Great Valley is an asymmetric trough, extending about 50 miles wide and 400 miles long. The southern portion of the Great Valley includes San Joaquin Valley filled with Pleistocene and Holocene alluvium derived from the Sierra Nevada and Coast Ranges. Sediments in the Great Valley are reportedly up to 40,000 feet thick.

Based on review of the Geologic Map of the Santa Cruz Quadrangle<sup>1</sup>, the area of the subject site is in an area mapped as Great Valley Fan Deposits (Qf).

## 8. GEOLOGIC HAZARDS

### 8.1. Faulting and Seismicity

Based on the proximity of several dominant active faults and seismogenic structures, as well as the historic seismic record, the area of the subject site is considered subject to relatively low to moderate seismicity. The project area is not within an Alquist-Priolo Special Studies Zone and will not require a special site

<sup>1</sup> Jennings, C.W., and Strand, R.G., 1958, Geologic map of the Santa Cruz Sheet, California, 1:250,000: California Division of Mines and Geology, Regional Geologic Map 5A, scale 1:250,000

investigation by an Engineering Geologist. Soils on site are classified as Site Class D in accordance with Chapter 16 of the California Building Code. The proposed structures are determined to be in Seismic Design Category D.

To determine the distance of known active faults within 100 miles of the site, we used the United States Geological Survey (USGS) web-based application *2008 National Seismic Hazard Maps - Fault Parameters*. Site latitude is 36.95000° North; site longitude is -120.0821° West. The ten closest active faults are summarized below in Table 8.1.

**TABLE 8.1**  
**REGIONAL FAULT SUMMARY**

<b>Fault Name</b>	<b>Distance to Site (miles)</b>	<b>Maximum Earthquake Magnitude, <math>M_w</math></b>
Great Valley 11	36.97	6.6
Great Valley 12	38.03	6.4
Great Valley 9	38.26	6.8
Great Valley 13 (Coalinga)	43.84	7.1
Ortogonalita	46.82	7.1
Great Valley 8	51.17	6.8
Great Valley 14 (Kettleman Hills)	56.52	7.2
San Andreas fault - creeping segment	62.83	N/A
Quien Sabe	64.14	6.6
Great Valley 7	69.00	6.9

*The faults tabulated above and numerous other faults in the region are sources of potential ground motion. However, earthquakes that might occur on other faults throughout California are also potential generators of significant ground motion and could subject the site to intense ground shaking.*

## **8.2. Surface Fault Rupture**

The site is not within a currently established State of California Earthquake Fault Zone for surface fault rupture hazards. No active faults with the potential for surface fault rupture are known to pass directly beneath the site. Therefore, the potential for surface rupture due to faulting occurring beneath the site during the design life of the proposed development is considered low.

## **8.3. Ground Shaking**

Based on the 2019 CBC, a site Class D was selected for the site based on soil conditions with standard penetration resistance, N-values, averaging between 15 and 50 blows per foot. Table 10.6.1 includes design seismic coefficients and spectral response parameters, based on the 2019 California Building Code (CBC) for the project foundation design.

Based on Office of Statewide Health Planning and Development (OSHPD) Seismic Design Maps, the estimated design peak ground acceleration adjusted for site class effects ( $PGA_M$ ) was determined to be 0.351 g (based on both probabilistic and deterministic seismic ground motion).

## **8.4. Liquefaction**

Soil liquefaction is a state of soil particles suspension caused by a complete loss of strength when the effective stress drops to zero. Liquefaction normally occurs under saturated conditions in soils such as sand

in which the strength is purely frictional. Primary factors that trigger liquefaction are: moderate to strong ground shaking (seismic source), relatively clean, loose granular soils (primarily poorly graded sands and silty sands), and saturated soil conditions (shallow groundwater). Due to the increasing overburden pressure with depth, liquefaction of granular soils is generally limited to the upper 50 feet of a soil profile.

The soils encountered appear typical of those found in the geologic region of the site. In general, the soils encountered predominantly consisted of firm to stiff sandy silty clay, underlain by medium dense sandy silt, clayey silty sand, and poorly graded sand with silt, to the maximum depth explored of 35 feet below site grade. Based on available water well data, historical high groundwater depths were reported at depths of about 19.6 feet below ground surface in May 1945.

A 50 foot deep test boring for the purpose of a site specific liquefaction/seismic settlement assessment was not included within the scope of this investigation. However, based on our experience in the Madera area, the relative density of the soils encountered during this investigation and the relatively low peak ground acceleration, the potential for liquefaction/seismic settlement to impact the site is considered low.

## **8.5. Lateral Spreading**

Lateral spreading is a phenomenon in which soils move laterally during seismic shaking and is often associated with liquefaction. The amount of movement depends on the soil strength, duration and intensity of seismic shaking, topography, and free face geometry. Due to the relatively flat site topography and lack of groundwater near the surface, we judge the likelihood of lateral spreading to be low.

## **8.6. Landslides**

There are no known landslides at the site, nor is the site in the path of any known or potential landslides. We do not consider the potential for a landslide to be a hazard to this project.

## **8.7. Tsunamis and Seiches**

The site is not located within a coastal area. Therefore, tsunamis (seismic sea waves) are not considered a significant hazard at the site.

Seiches are large waves generated in enclosed bodies of water in response to ground shaking. No major water-retaining structures are located immediately up gradient from the project site. Flooding from a seismically-induced seiche is considered unlikely.

# **9. CONCLUSIONS AND RECOMMENDATIONS**

## **9.1. General Conclusions**

- 9.1.1 Based upon the data collected during this investigation, and from a geotechnical engineering standpoint, it is our opinion that the site is suitable for the proposed construction of improvements at the site as planned, provided the recommendations contained in this report are incorporated into the project design and construction. Conclusions and recommendations provided in this report are based on our review of available literature, analysis of data obtained from our field exploration and laboratory testing program, and our understanding of the proposed development at this time.
- 9.1.2 The subsurface conditions encountered are consistent with those found in the geologic region of the site. Cemented soils locally referred to as “Hardpan” was encountered at depths between about 8 feet and 16 feet below site grade in exploratory test borings. In general, the soils encountered

predominantly consisted of firm to stiff sandy silty clay, underlain by medium dense sandy silt, clayey silty sand, and poorly graded sand with silt, to the maximum depth explored of 35 feet below site grade.

- 9.1.3 The near surface soils have a very low expansion potential.
- 9.1.4 Based on the subsurface conditions at the site and the anticipated structural loading, we anticipate that the proposed structures may be supported using conventional shallow foundations provided that the recommendations presented herein are incorporated in the design and construction of the project.
- 9.1.5 Provided the site is graded in accordance with the recommendations of this report and foundations constructed as described herein, we estimate that total settlement due to static loads utilizing conventional shallow foundations for the proposed building will be within 1-inch and corresponding differential settlement will be less than ½-inch in 40 feet.
- 9.1.6 Based on the chemistry testing performed, the near surface soils have “negligible” potential for sulfate attack on concrete and a “moderately corrosive” potential to buried metal objects (per National Association of Corrosion Engineers, Corrosion Severity Ratings).
- 9.1.7 All references to relative compaction and optimum moisture content in this report are based on ASTM D 1557 (latest edition).
- 9.1.8 We should be retained to review the project plans as they develop further, provide engineering consultation as-needed, and perform geotechnical observation and testing services during construction.

## **9.2. Surface Drainage and Storm Water Basin Design and Maintenance**

- 9.2.1 Proper surface drainage is critical to the future performance of the project. Uncontrolled infiltration of irrigation excess and storm runoff into the soils can adversely affect the performance of the planned improvements. Saturation of a soil can cause it to lose internal shear strength and increase its compressibility, resulting in a change to important engineering properties. Proper drainage should be maintained at all times.
- 9.2.2 The ground immediately adjacent to the foundation shall be sloped away from the building at a slope of not less than 5 percent for a minimum distance of 10 feet. Impervious surfaces within 10 feet of the building foundation shall be sloped a minimum of 2 percent away from the building and drainage gradients maintained to carry all surface water to collection facilities and off site. These grades should be maintained for the life of the project. Ponding of water should not be allowed adjacent to the structure. Over-irrigation within landscaped areas adjacent to the structure should not be performed.
- 9.2.3 Roof drains should be installed with appropriate downspout extensions out-falling on splash blocks so as to direct water a minimum of 5 feet away from the structures or be connected to the storm drain system for the development.
- 9.2.4 Considering the results of percolation testing a maximum unfactored infiltration rate of 0.1 inches per hour is recommended for design.
- 9.2.5 Field testing is a small-scale test method and does not take into account the long term effects of subgrade saturation, silt/fines accumulation, infrequent maintenance, or mechanical densification

of the soils as a result of the construction process, etc. Thus, a safety factor should be applied by the basin designer to the estimated unfactored infiltration rates. A safety factor ranging from 3 to 10 is generally recommended; however, the final safety factor should also meet the requirements of the governing agency and should consider such factors as the sediment load of the storm water, whether pretreatment of storm water is planned, the consequences of failure, the degree of maintenance that can be relied upon and the uncertainties in the estimated inflow volume.

- 9.2.6 Infiltration systems, such as storm water basins, should not be located within 20 feet of proposed building(s) due to the potential for foundation settlement.
- 9.2.7 Basin side slopes should not be steeper than 3H to 1V, and flatter if possible, to reduce the potential for erosion. Basins should be designed with ramps to allow for maintenance equipment access to the bottom and sides of the basin.
- 9.2.8 Regular maintenance should be expected to maximize the useful life of the basin. Periodic maintenance should be conducted and should include removal of trash, debris, vegetation, siltation and fine particles (e.g. silts and organic matter), and performing drainage improvements to reduce the sediment load in the runoff. Lightweight equipment should be used for these activities to minimize compaction of the infiltration surfaces.

### **9.3. Site Grading**

- 9.3.1 A representative of our firm should be present during all site clearing and grading operations to test and/or observe earthwork construction. This testing and observation is an integral part of our service as acceptance of earthwork construction is dependent upon compaction of the material and the stability of the material. The Geotechnical Engineer may reject any material that does not meet compaction and stability requirements. Further recommendations of this report are predicated upon the assumption that earthwork construction will conform to recommendations set forth in this section as well as other portions of this report.
- 9.3.2 A preconstruction conference should be held at the site prior to the beginning of grading operations with the owner, contractor, civil engineer and geotechnical engineer in attendance.
- 9.3.3 Site demolition activities shall include removal of all surface obstructions not intended to be incorporated into final site design. In addition, undocumented fill, underground buried structures, and/or utility lines, underground septic tanks and leach lines (if any), existing foundation elements, etc., encountered during demolition and construction should be properly removed and the resulting excavations backfilled with Engineered Fill. After demolition activities, it is recommended that disturbed soils be removed and/or replaced with compacted engineered fill soils.
- 9.3.4 Excavations or depressions resulting from site clearing/demolition operations, or other existing excavations or depressions, should be restored with Engineered Fill in accordance with the recommendations of this report.
- 9.3.5 Surface vegetation consisting of grasses and other similar vegetation should be removed by stripping to a sufficient depth to remove organic-rich topsoil. The upper 2 to 4 inches of the soils containing, vegetation, roots and other objectionable organic matter encountered at the time of grading should be stripped and removed from the surface. Deeper stripping may be required in localized areas. The stripped vegetation will not be suitable for use as Engineered Fill or within 5 feet of building pads. However, stripped topsoil may be stockpiled and reused in landscape or non-structural areas or exported from the site.

- 9.3.6 Structural building pad areas and over-build zone should be considered as areas extending a minimum of 5 feet horizontally beyond the outside dimensions of buildings, including footings and non-cantilevered overhangs carrying structural loads.
- 9.3.7 To provide uniform support for the proposed buildings, it is recommended that over-excavation extend to the bottom of proposed foundations, 24 inches below preconstruction site grades, or to the depth to remove loose/disturbed soils, whichever is greater. The resulting over-excavation shall be scarified to a depth of at least 12 inches, worked until uniform and free from large clods, moisture-conditioned to slightly above optimum moisture, and compacted to a minimum of 92 percent of the maximum density. The horizontal limits of the over-excavation should extend throughout the building over-build zone, laterally to a minimum of 5 feet beyond the outer edges of the proposed footings.
- 9.3.8 Interior slabs on grade should be supported on a minimum of 4 inches of Class 2 aggregate base over the depth of engineered fill recommended below foundations. As an alternative if the Owner is willing to accept risk for subgrade disturbance the Class 2 aggregate base may be replaced by a sand blotter specified by the slab designer.
- 9.3.9 Areas of exterior concrete slabs on grade located outside the building pad over-build zone, should be prepared by over-excavation to a minimum of 12 inches below existing grade or 12 inches below the bottom of concrete slabs, whichever is greater. The zone of over-excavation should extend a minimum of 3 feet beyond these improvements. These soils should be moisture conditioned to slightly above optimum and compacted as engineered fill.
- Exterior concrete slabs on grade should be supported on a minimum of 4 inches of Class 2 aggregate base compacted to 95 percent relative compaction over engineered fill prepared as recommended above. If the Owner is willing to accept risk for slab distress, the use of Class 2 aggregate base may be omitted for exterior concrete slabs.
- 9.3.10 Areas of asphaltic concrete pavements (if any), Portland cement concrete pavements and gravel drive areas located outside the building pad over-build zone, should be prepared by over-excavation to a minimum of 12 inches below existing grade or 12 inches below the bottom of base section, whichever is greater. The zone of over-excavation should extend a minimum of 3 feet beyond these improvements. These soils should be moisture conditioned to near optimum and compacted as engineered fill. The upper 12 inches below pavements should be compacted to 95 percent relative compaction.
- 9.3.11 Areas to receive engineered fill outside the building pad over-build zone, should be prepared by scarification of the upper 12 inches below existing grade or 12 inches below the recommended base section, whichever is greater. These soils should be moisture conditioned to slightly above optimum and compacted as engineered fill.
- 9.3.12 An integral part of satisfactory fill placement is the stability of the placed lift of soil. If placed materials exhibit excessive instability as determined by a SALEM field representative, the lift will be considered unacceptable and shall be remedied prior to placement of additional fill material. Additional lifts should not be placed if the previous lift did not meet the required dry density or if soil conditions are not stable.



- 9.3.13 The most effective site preparation alternatives will depend on site conditions prior to grading. We should evaluate site conditions and provide supplemental recommendations immediately prior to grading, if necessary.
- 9.3.14 We do not anticipate groundwater or seepage to adversely affect construction if conducted during the drier months of the year (typically summer and fall). However, groundwater and soil moisture conditions could be significantly different during the wet season (typically winter and spring) as surface soil becomes wet; perched groundwater conditions may develop. Grading during this time period will likely encounter wet materials resulting in possible excavation and fill placement difficulties. Project site winterization consisting of placement of aggregate base and protecting exposed soils during construction should be performed. If the construction schedule requires grading operations during the wet season, we can provide additional recommendations as conditions warrant.
- 9.3.15 Typical remedial measures include: discing and aerating the soil during dry weather; mixing the soil with dryer materials; removing and replacing the soil with an approved fill material or placement of crushed rocks or aggregate base material; or mixing the soil with an approved lime or cement product.

The most common remedial measure of stabilizing the bottom of the excavation due to wet soil condition is to reduce the moisture of the soil to near the optimum moisture content by having the subgrade soils scarified and aerated or mixed with drier soils prior to compacting. However, the drying process may require an extended period of time and delay the construction operation. To expedite the stabilizing process, crushed rock may be utilized for stabilization provided this method is approved by the owner for the cost purpose.

If the use of crushed rock is considered, it is recommended that the upper soft and wet soils be replaced by 6 to 24 inches of  $\frac{3}{4}$ -inch to 1-inch crushed rocks. The thickness of the rock layer depends on the severity of the soil instability. The recommended 6 to 24 inches of crushed rock material will provide a stable platform. It is further recommended that lighter compaction equipment be utilized for compacting the crushed rock. All open graded crushed rock/gravel should be fully encapsulated with a geotextile fabric (such as Mirafi 140N) to minimize migration of soil particles into the voids of the crushed rock. Although it is not required, the use of geogrid (e.g. Tensar BX 1100, BX 1200 or TX 160) below the crushed rock will enhance stability and reduce the required thickness of crushed rock necessary for stabilization.

In addition, chemical drying of the bottom of the excavation and engineered fill soils could be considered. For bidding purposes, the Contractor may assume 5 percent high calcium quicklime for chemical stabilization/drying of on-site soils. The actual application rate will need to be adjusted based on conditions encountered during grading.

Our firm should be consulted prior to implementing remedial measures to provide appropriate recommendations.

#### **9.4. Soil and Excavation Characteristics**

- 9.4.1 Based on the soil conditions encountered in our borings, the onsite soils can be excavated with moderate effort using conventional excavation equipment. As noted, hardpan soils were encountered at various depths ranging from 8 and 16 feet below site grade. The contractor should anticipate deeper excavations may require increased excavation effort.

- 9.4.2 It is the responsibility of the contractor to ensure that all excavations and trenches are properly shored and maintained in accordance with applicable Occupational Safety and Health Administration (OSHA) rules and regulations to maintain safety and maintain the stability of adjacent existing improvements. Temporary excavations are further discussed in a later Section of this report.
- 9.4.3 The near surface soils identified as part of our investigation are, generally, damp to moist due to the absorption characteristics of the soil. Earthwork operations may encounter very moist unstable soils which may require removal to a stable bottom. Exposed native soils exposed as part of site grading operations should not be allowed to dry out and should be kept continuously moist prior to placement of subsequent fill.

## 9.5. Materials for Fill

- 9.5.1 On-site soils are suitable for use as general Engineered Fill provided they do not contain deleterious matter, organic material, or rock/cemented soil fragments material larger than 3 inches in maximum dimension.
- 9.5.2 Imported Engineered Fill soil, should be well-graded, very low-to-non-expansive slightly cohesive silty sand or sandy silt. This material should be approved by the Engineer prior to use and should typically possess the soil characteristics summarized below in Table 9.5.2

**TABLE 9.5.2  
IMPORT FILL REQUIREMENTS**

Percent Passing 3-inch Sieve	100
Percent Passing No.4 Sieve	75-100
Percent Passing No 200 Sieve	15-40
Maximum Plasticity Index	15
Organic Content, Percent by Weight	Less than 3%
Maximum Expansion Index (ASTM D4829)	20

Prior to importing the Contractor should demonstrate to the Owner that the proposed import meets the requirements for import fill specified in this report. In addition, the material should be verified by the Contractor that the soils do not contain any environmental contaminants as regulated by local, state, or federal agencies, as applicable

- 9.5.3 All Engineered Fill (including scarified ground surfaces and backfill) should be placed in lifts no thicker than will allow for adequate bonding and compaction (typically 6 to 8 inches in loose thickness).
- 9.5.4 On-Site soils used as engineered fill soils should be moisture conditioned to slightly above optimum moisture content and compacted to at least 92 percent relative compaction (ASTM D1557).
- 9.5.5 Import Engineered Fill, if selected, should be placed, moisture conditioned to slightly above optimum moisture content, and compacted to at least 92 percent relative compaction (ASTM D1557).



- 9.5.6 The preferred materials specified for Engineered Fill are suitable for most applications with the exception of exposure to erosion. Project site winterization and protection of exposed soils during the construction phase should be the sole responsibility of the Contractor, since they have complete control of the project site.
- 9.5.7 Environmental characteristics and corrosion potential of import soil materials should also be considered.
- 9.5.8 Proposed import materials should be sampled, tested, and approved by SALEM prior to its transportation to the site.
- 9.5.9 Aggregate base material should meet the requirements of a Caltrans Class 2 Aggregate Base. The aggregate base material should conform to the requirements of Section 26 of the Standard Specifications for Class 2 material, ¾-inch or 1½-inches maximum size. The aggregate base material should be compacted to a minimum relative compaction of 95 percent based ASTM D1557. The aggregate base material should be spread in layers not exceeding 6 inches and each layer of aggregate material course should be tested and approved by the Soils Engineer prior to the placement of successive layers
- 9.6. Seismic Design Criteria**
- 9.6.1 For seismic design of the structures, and in accordance with the seismic provisions of the 2019 CBC, our recommended parameters are shown below. These parameters were determined using California’s Office of Statewide Health Planning and Development (OSHPD) (<https://seismicmaps.org/>) in accordance with the 2019 CBC. The Site Class was determined based on the soils encountered during our field exploration.

**TABLE 9.6.1**  
**2019 CBC SEISMIC DESIGN PARAMETERS**

Seismic Item	Symbol	Value	2016 ASCE 7 or 2019 CBC Reference
Site Coordinates (Datum = NAD 83)		36.95000 Lat -120.0821 Lon	
Site Class	--	D	ASCE 7 Table 20.3
Soil Profile Name	--	“ Stiff Soil ”	ASCE 7 Table 20.3
Risk Category	--	II	CBC Table 1604.5
Site Coefficient for PGA	F <sub>PGA</sub>	1.338	ASCE 7 Table 11.8-1
Peak Ground Acceleration (adjusted for Site Class effects)	PGA <sub>M</sub>	0.351	ASCE 7 Equation 11.8-1
Seismic Design Category	SDC	D	ASCE 7 Table 11.6-1 & 2
Mapped Spectral Acceleration (Short period - 0.2 sec)	S <sub>S</sub>	0.608 g	CBC Figure 1613.3.1(1-6)
Mapped Spectral Acceleration (1.0 sec. period)	S <sub>1</sub>	0.237 g	CBC Figure 1613.3.1(1-6)
Site Class Modified Site Coefficient	F <sub>a</sub>	1.314	CBC Table 1613.3.3(1)

Seismic Item	Symbol	Value	2016 ASCE 7 or 2019 CBC Reference
Site Class Modified Site Coefficient	$F_v$	<b>2.126*</b>	CBC Table 1613.3.3(2)
MCE Spectral Response Acceleration (Short period - 0.2 sec) $S_{MS} = F_a S_s$	$S_{MS}$	0.798 g	CBC Equation 16-37
MCE Spectral Response Acceleration (1.0 sec. period) $S_{M1} = F_v S_1$	$S_{M1}$	<b>0.504 g*</b>	CBC Equation 16-38
Design Spectral Response Acceleration $S_{DS} = \frac{2}{3} S_{MS}$ (short period - 0.2 sec)	$S_{DS}$	0.532 g	CBC Equation 16-39
Design Spectral Response Acceleration $S_{D1} = \frac{2}{3} S_{M1}$ (1.0 sec. period)	$S_{D1}$	<b>0.336 g*</b>	CBC Equation 16-40
Short Period Transition Period ( $S_{D1}/S_{DS}$ ), Seconds	$T_s$	0.631	ASCE 7-16, Section 11.4.6
Long Period Transition Period (seconds)	$T_L$	12	ASCE 7-16, Figures 22-14 through 22-17

Note: \* Determined per ASCE 11.4 for use in calculating  $T_s$  only.

Site Specific Ground Motion Analysis was not included in the scope of this investigation. Per ASCE 11.4.8, Structures on Site Class D, with  $S_1$  greater than or equal to 0.2 may require Site Specific Ground Motion Analysis. However, a site specific ground motion analysis may not be required based on Exceptions listed in ASCE 11.4.8. The Structural Engineer should verify whether Exception No. 2 of ASCE 7-16, Section 11.4.8 is valid for the proposed construction. In the event a site specific ground motion analysis is required, SALEM should be contacted for these services.

9.6.2 Conformance to the criteria in the above table for seismic design does not constitute any kind of guarantee or assurance that significant structural damage or ground failure will not occur if a large earthquake occurs. The primary goal of seismic design is to protect life, not to avoid all damage, since such design may be economically prohibitive.

## 9.7. Shallow Foundations

9.7.1 The site is suitable for use of conventional shallow foundations consisting of continuous footings and isolated pad footings supported on engineered fill soils prepared in accordance with Section 9.3 of this report. Shallow foundations supported on engineered fill as recommended in this report may be designed based on total and differential static settlement of 1 inch and ½ inch in 40 feet, respectively.

9.7.2 Perimeter wall bearing footings considered for the structure should be continuous with a minimum width of 15 inches and extend to minimum depths of 12 inches below the lowest adjacent grade. Isolated column footings should have a minimum width of 15 inches and extend a minimum depth of 12 inches below the lowest adjacent grade.

9.7.3 Footing concrete should be placed into neat excavation. The footing bottoms shall be maintained free of loose and disturbed soil.

9.7.4 Foundations supported on engineered fill as recommended in this report may be designed based on an allowable bearing capacity of 2,000 pounds per square foot. This value may be increased by one-third for wind and seismic loading.

- 9.7.5 Resistance to lateral footing displacement can be computed using an allowable coefficient of friction factor of 0.38 acting between the base of foundations and the engineered fills.
- 9.7.6 Lateral resistance for footings can alternatively be developed using an allowable equivalent fluid passive pressure of 350 pounds per cubic foot acting against the appropriate vertical footing faces. The frictional and passive resistance of the soil may be combined without reduction in determining the total lateral resistance. An increase of one-third is permitted when using the alternate load combination in Section 1605.3.2 of the 2019 CBC that includes wind or earthquake loads.
- 9.7.7 Underground utilities running parallel to footings should not be constructed in the zone of influence of footings. The zone of influence may be taken to be the area beneath the footing and within a 1:1 plane extending out and down from the bottom edge of the footing.
- 9.7.8 The foundation subgrade should be sprinkled as necessary to maintain a moist condition without significant shrinkage cracks as would be expected in any concrete placement. Prior to placing rebar reinforcement, foundation excavations should be evaluated by a representative of SALEM for appropriate support characteristics and moisture content. Moisture conditioning may be required for the materials exposed at footing bottom, particularly if foundation excavations are left open for an extended period.

## **9.8. Interior Concrete Slabs-on-Grade**

- 9.8.1 Slab thickness and reinforcement should be determined by the structural engineer based on the anticipated loading. We recommend that non-structural slabs-on-grade be at least 5 inches thick and underlain by four (4) inches of class 2 aggregate base over the thickness of compacted engineered fill extending below foundations. As an alternative if the Owner is willing to accept risk for subgrade disturbance the Class 2 aggregate base may be replaced by a sand blotter specified by the slab designer.
- 9.8.2 We recommend reinforcing slabs, at a minimum, with No. 3 reinforcing bars placed 18 inches on center, each way. If the owner is willing to accept additional risk for slab cracking, alternatives such as wire mesh or fiber reinforcement may be considered.
- 9.8.3 The spacing of crack control joints should be designed by the project structural engineer. In order to regulate cracking of the slabs, we recommend that full depth construction joints or control joints be provided at a maximum spacing of 15 feet in each direction for 5-inch thick slabs and 12 feet for 4-inch thick slabs.
- 9.8.4 Crack control joints should extend a minimum depth of one-fourth the slab thickness and should be constructed using saw-cuts or other methods as soon as practical after concrete placement. The exterior floors should be poured separately in order to act independently of the walls and foundation system.
- 9.8.5 It is recommended that the utility trenches within the structure be compacted, as specified in our report, to minimize the transmission of moisture through the utility trench backfill. Special attention to the immediate drainage and irrigation around the structures is recommended.
- 9.8.6 Moisture within the structure may be derived from water vapors, which were transformed from the moisture within the soils. This moisture vapor penetration can affect floor coverings and produce mold and mildew in the structure. To minimize moisture vapor intrusion, it is recommended that a vapor retarder be installed in accordance with manufacturer's recommendations and/or ASTM

guidelines, whichever is more stringent. In addition, ventilation of the structure is recommended to reduce the accumulation of interior moisture.

- 9.8.7 In areas where it is desired to reduce floor dampness where moisture-sensitive coverings, coatings, underlayments, adhesives, moisture sensitive goods, humidity controlled environments, or climate cooled environments are anticipated, construction should have a suitable waterproof vapor retarder (a minimum of 15 mils thick, is recommended, polyethylene vapor retarder sheeting, Raven Industries “VaporBlock 15, Stego Industries 15 mil “StegoWrap” or W.R. Meadows Sealtight 15 mil “Perminator”) incorporated into the floor slab design. The water vapor retarder should be a decay resistant material complying with ASTM E96 or ASTM E1249 not exceeding 0.01 perms, ASTM E154 and ASTM E1745 Class A. The vapor retarder should, maintain the recommended permeance **after** conditioning tests per ASTM E1745. The vapor barrier should be placed between the concrete slab and the compacted granular aggregate subbase material. The water vapor retarder (vapor barrier) should be installed in accordance with ASTM Specification E 1643-18.
- 9.8.8 The concrete maybe placed directly on vapor retarder. The vapor retarder should be inspected prior to concrete placement. Cut or punctured retarder should be repaired using vapor retarder material lapped 6 inches beyond damaged areas and taped. Extend vapor retarder over footings and seal to foundation wall or slab at an elevation consistent with the top of the slab or terminate at impediments such as water stops or dowels. Seal around penetrations such as utilities or columns in order to create a monolithic membrane between the surface of the slab and moisture sources below the slab as well as at the slab perimeter.
- 9.8.9 Avoid use of stakes driven through the vapor retarder.
- 9.8.10 The recommendations of this report are intended to reduce the potential for cracking of slabs due to soil movement. However, even with the incorporation of the recommendations presented herein, foundations, stucco walls, and slabs-on-grade may exhibit some cracking due to soil movement. This is common for project areas that contain expansive soils since designing to eliminate potential soil movement is cost prohibitive. The occurrence of concrete shrinkage cracks is independent of the supporting soil characteristics. Their occurrence may be reduced and/or controlled by limiting the slump of the concrete, proper concrete placement and curing, and by the placement of crack control joints at periodic intervals, in particular, where re-entrant slab corners occur.
- 9.8.11 Proper finishing and curing should be performed in accordance with the latest guidelines provided by the American Concrete Institute, Portland Cement Association, and ASTM.

## **9.9. Exterior Slabs on Grade**

- 9.9.1 The following recommendations are intended for lightly loaded exterior slabs on grade not subject to vehicular traffic. Slab thickness and reinforcement should be determined by the structural engineer based on the anticipated loading. We recommend that non-structural slabs-on-grade be at least 4 inches thick and underlain by four (4) inches of class 2 aggregate base over the depth of compacted engineered fill recommended in section 9.3 of this report. If the Owner is willing to accept risk for slab distress, the use of class 2 aggregate base may be omitted for exterior concrete slabs.
- 9.9.2 The spacing of crack control joints should be designed by the project structural engineer. In order to regulate cracking of the slabs, we recommend that full depth construction joints or control joints

be provided at a maximum spacing of 15 feet in each direction for 5-inch thick slabs and 12 feet for 4-inch thick slabs.

- 9.9.3 Crack control joints should extend a minimum depth of one-fourth the slab thickness and should be constructed using saw-cuts or other methods as soon as practical after concrete placement.
- 9.9.4 Proper finishing and curing should be performed in accordance with the latest guidelines provided by the American Concrete Institute, Portland Cement Association, and ASTM.

#### 9.10. Lateral Earth Pressures and Frictional Resistance

- 9.10.1. Active, at-rest and passive unit lateral earth pressures against footings and walls are summarized in the table below:

Lateral Pressure Conditions	Soil Equivalent Fluid Pressure
Active Pressure, Drained, pcf	31
At-Rest Pressure, Drained, pcf	50
Allowable Passive Pressure, pcf	350
Allowable Coefficient of Friction	0.38
Minimum Wet Unit Weight (lbs/ft <sup>3</sup> ) [ $\gamma_{min}$ ]	100
Maximum Wet Unit Weight (lbs/ft <sup>3</sup> ) [ $\gamma_{max}$ ]	135

- 9.10.2. Active pressure applies to walls, which are free to rotate. At-rest pressure applies to walls, which are restrained against rotation. The preceding lateral earth pressures assume sufficient drainage behind retaining walls to prevent the build-up of hydrostatic pressure. The top one-foot of adjacent subgrade should be deleted from the passive pressure computation.
- 9.10.3. The allowable parameters include a safety factor of 1.5 and can be used in design for direct comparison of resisting loads against lateral driving loads.
- 9.10.4. If combined passive and frictional resistance is used in design, a 50 percent reduction in frictional resistance is recommended.
- 9.10.5. For lateral stability against seismic loading conditions, we recommend a minimum safety factor of 1.1.
- 9.10.6. For dynamic seismic lateral loading the following equation shall be used:

Dynamic Seismic Lateral Loading Equation
Dynamic Seismic Lateral Load = $\frac{3}{8}\gamma K_h H^2$
Where: $\gamma$ = Maximum In-Place Soil Density (Section 9.10.1 above)
$K_h$ = Horizontal Acceleration = $\frac{2}{3}PGA_M$ (Section 9.6.1 above)
H = Wall Height

## 9.11. Temporary Excavations

- 9.11.1. We anticipate that the majority of the dense site soils will be classified as Cal-OSHA “Type C” soil when encountered in excavations during site development and construction. If the subgrade becomes unstable due to excessive moisture, the excavations should conform to Cal-OSHA “Type C” soil. Excavation sloping, benching, the use of trench shields, and the placement of trench spoils should conform to the latest applicable Cal-OSHA standards. The contractor should have a Cal-OSHA-approved “competent person” onsite during excavation to evaluate trench conditions and make appropriate recommendations where necessary.
- 9.11.2. It is the contractor’s responsibility to provide sufficient and safe excavation support as well as protecting nearby utilities, structures, and other improvements which may be damaged by earth movements. All onsite excavations must be conducted in such a manner that potential surcharges from existing structures, construction equipment, and vehicle loads are resisted. The surcharge area may be defined by a 1:1 projection down and away from the bottom of an existing foundation or vehicle load.
- 9.11.3. Temporary excavations and slope faces should be protected from rainfall and erosion. Surface runoff should be directed away from excavations and slopes.
- 9.11.4. Open, unbraced excavations in undisturbed soils should be made according to the slopes presented in the following table:

**RECOMMENDED EXCAVATION SLOPES**

Depth of Excavation (ft)	Slope (Horizontal : Vertical)
0-5	1:1
5-10	1½:1
10-15	2:1

- 9.11.5. If, due to space limitation, excavations near existing structures are performed in a vertical position, braced shorings or shields may be used for supporting vertical excavations. Therefore, in order to comply with the local and state safety regulations, a properly designed and installed shoring system would be required to accomplish planned excavations and installation. A Specialty Shoring Contractor should be responsible for the design and installation of such a shoring system during construction.
- 9.11.6. Braced shorings should be designed for a maximum pressure distribution of 25H, (where H is the depth of the excavation in feet). The foregoing does not include excess hydrostatic pressure or surcharge loading. Fifty percent of any surcharge load, such as construction equipment weight, should be added to the lateral load given herein. Equipment traffic should concurrently be limited to an area at least 3 feet from the shoring face or edge of the slope.
- 9.11.7. The excavation and shoring recommendations provided herein are based on soil characteristics derived from the borings within the area. Variations in soil conditions will likely be encountered during the excavations. SALEM Engineering Group, Inc. should be afforded the opportunity to provide field review to evaluate the actual conditions and account for field condition variations not otherwise anticipated in the preparation of this recommendation. Slope height, slope inclination, or



excavation depth should in no case exceed those specified in local, state, or federal safety regulation, (e.g. OSHA) standards for excavations, 29 CFR part 1926, or Assessor's regulations.

## **9.12. Underground Utilities**

- 9.12.1. Underground utility trenches should be backfilled with properly compacted material. The material excavated from the trenches should be adequate for use as backfill provided it does not contain deleterious matter, vegetation or rock larger than 3 inches in maximum dimension. Trench backfill should be placed in loose lifts not exceeding 8 inches and compacted to at least 92 percent relative compaction at or above optimum moisture content. The upper 12 inches of trench backfill within asphalt or concrete paved areas shall be moisture conditioned to at or above optimum moisture content and compacted to at least 95 percent relative compaction.
- 9.12.2. Bedding and pipe zone backfill typically extends from the bottom of the trench excavations to approximately 12 inches above the crown of the pipe. Pipe bedding, haunches and initial fill extending to 1 foot above the pipe should consist of a clean well graded sand with 100 percent passing the #4 sieve, a maximum of 15 percent passing the #200 sieve, and a minimum sand equivalent of 20.
- 9.12.3. It is suggested that underground utilities crossing beneath new or existing structures be plugged at entry and exit locations to the building or structure to prevent water migration. Trench plugs can consist of on-site clay soils, if available, or sand cement slurry. The trench plugs should extend 2 feet beyond each side of individual perimeter foundations.
- 9.12.4. The contractor is responsible for removing all water-sensitive soils from the trench regardless of the backfill location and compaction requirements. The contractor should use appropriate equipment and methods to avoid damage to the utilities and/or structures during fill placement and compaction.

## **9.13 Pavement Design**

- 9.13.1 R-value testing was not included in the scope of this investigation. Based on the results of the laboratory tests performed an R-value of 50 was used for design.
- 9.13.2 The asphaltic concrete (flexible pavement) is based on a 20-year pavement life utilizing traffic indexes of ranging from 4.0 and 6.0. The Civil Engineer should select the appropriate pavement section based on the anticipated traffic loading. The following table shows the recommended pavement sections for various traffic indices.

**TABLE 9.13.2**  
**ASPHALT CONCRETE PAVEMENT THICKNESSES**

<b>Traffic Index</b>	<b>Asphaltic Concrete, (inches)</b>	<b>Class 2 Aggregate Base, (inches)*</b>	<b>Compacted Subgrade, (inches)*</b>
4.0	2.5	4.0	12.0
5.0	2.5	4.0	12.0
6.0	3.0	4.0	12.0

*\*95% compaction based on ASTM D1557 Test Method*

9.13.3 The following recommendations are for Portland Cement Concrete pavement sections.

**TABLE 9.13.3**  
**PORTLAND CEMENT CONCRETE PAVEMENT THICKNESSES**

<b>Traffic Index</b>	<b>Portland Cement Concrete, (inches)*</b>	<b>Class 2 Aggregate Base, (inches)**</b>	<b>Compacted Subgrade. (inches)**</b>
4.0	4.5	4.0	12.0
5.0	5.0	4.0	12.0
6.0	6.0	4.0	12.0

\* Minimum Compressive Strength of 4,000 psi  
\*\* 95% compaction based on ASTM D1557 Test Method

- 9.13.4 Asphalt concrete should conform to Section 39 of Caltrans' latest Standard Specifications for ½ inch Hot Mix Asphalt (HMA) Type A or B. Asphaltic concrete pavements should be placed and compacted in accordance with Caltrans Standard Specifications.
- 9.13.5 Excavations, depressions, or soft and pliant areas extending below planned finished subgrade levels should be cleaned to firm, undisturbed soil and backfilled with Engineered Fill. Any buried structures encountered during construction should be properly removed and backfilled.
- 9.13.6 Buried structures encountered during construction should be properly removed/rerouted and the resulting excavations backfilled. It is suspected that demolition activities of the existing pavement will disturb the upper soils. After demolition activities, it is recommended that disturbed soils within pavement areas be removed and/or compacted as engineered fill.
- 9.13.7 An integral part of satisfactory fill placement is the stability of the placed lift of soil. Prior to placement of aggregate base, the subgrade soils should be proof-rolled by a loaded water truck (or equivalent) to verify no deflections of greater than ½ inch occur. If placed materials exhibit excessive instability as determined by a SALEM field representative, the lift will be considered unacceptable and should be remedied prior to placement of additional fill material. Additional lifts should not be placed if the previous lift did not meet the required dry density or if soil conditions are not stable.
- 9.13.8 A representative of our firm should be present during all site clearing and grading operations to test and observe earthwork construction. This testing and observation is an integral part of our service as acceptance of earthwork construction is dependent upon compaction of the material and the stability of the material.

## **10. PLAN REVIEW, CONSTRUCTION OBSERVATION AND TESTING**

### **10.1. Plan and Specification Review**

- 10.1.1 SALEM should review the project plans and specifications prior to final design submittal to assess whether our recommendations have been properly implemented and evaluate if additional analysis and/or recommendations are required.



## **10.2. Construction Observation and Testing Services**

- 10.2.1 The recommendations provided in this report are based on the assumption that we will continue as Geotechnical Engineer of Record throughout the construction phase. It is important to maintain continuity of geotechnical interpretation and confirm that field conditions encountered are similar to those anticipated during design. If we are not retained for these services, we cannot assume any responsibility for others interpretation of our recommendations, and therefore the future performance of the project.
- 10.2.2 SALEM should be present at the site during site preparation to observe site clearing, preparation of exposed surfaces after clearing, and placement, treatment and compaction of fill material.
- 10.2.3 SALEM's observations should be supplemented with periodic compaction tests to establish substantial conformance with these recommendations. Moisture content of footings and slab subgrade should be tested immediately prior to concrete placement. SALEM should observe foundation excavations prior to placement of reinforcing steel or concrete to assess whether the actual bearing conditions are compatible with the conditions anticipated during the preparation of this report.

## **11. LIMITATIONS AND CHANGED CONDITIONS**

The analyses and recommendations submitted in this report are based upon the data obtained from the test borings drilled at the approximate locations shown on the Site Plan, Figure 1. The report does not reflect variations which may occur between borings. The nature and extent of such variations may not become evident until construction is initiated.

If variations then appear, a re-evaluation of the recommendations of this report will be necessary after performing on-site observations during the excavation period and noting the characteristics of such variations. The findings and recommendations presented in this report are valid as of the present and for the proposed construction. If site conditions change due to natural processes or human intervention on the property or adjacent to the site, or changes occur in the nature or design of the project, or if there is a substantial time lapse between the submission of this report and the start of the work at the site, the conclusions and recommendations contained in our report will not be considered valid unless the changes are reviewed by SALEM and the conclusions of our report are modified or verified in writing. The validity of the recommendations contained in this report is also dependent upon an adequate testing and observations program during the construction phase. Our firm assumes no responsibility for construction compliance with the design concepts or recommendations unless we have been retained to perform the on-site testing and review during construction. SALEM has prepared this report for the exclusive use of the owner and project design consultants.

SALEM does not practice in the field of corrosion engineering. It is recommended that a qualified corrosion engineer be consulted regarding protection of buried steel or ductile iron piping and conduit or, at a minimum, that manufacturer's recommendations for corrosion protection be closely followed. Further, a corrosion engineer may be needed to incorporate the necessary precautions to avoid premature corrosion of concrete slabs and foundations in direct contact with native soil. The importation of soil and or aggregate materials to the site should be screened to determine the potential for corrosion to concrete and buried metal piping. The report has been prepared in accordance with generally accepted geotechnical engineering practices in the area. No other warranties, either express or implied, are made as to the professional advice provided under the terms of our agreement and included in this report.

If you have any questions, or if we may be of further assistance, please do not hesitate to contact our office at (559) 271-9700.

Respectfully Submitted,

**SALEM ENGINEERING GROUP, INC.**



Ahmad Dalqamouni, Ph.D, M.CE.  
Geotechnical Project Manager




Dean B. Ledgerwood II, EIT, PG, CEG  
Geotechnical Manager  
PG 8725 / CEG 2613



R. Sammy Salem, PE, GE  
Principal Managing Engineer  
RCE 52762 / RGE 2549





Madera, CA. 2018 USGS 7.5' Topo

## VICINITY MAP

PROPOSED STORAGE BUILDINGS  
S. SCHNOOR STREET  
MADERA, CALIFORNIA

SCALE: 1 : 2500'

DRAWN BY: VT


PROJECT NO. 1-221-0369


DATE: April 2021

APPROVED BY: DL

FIGURE NO. 1





SITE PLAN	SCALE: 1" = 200'	DATE: April 2021	 <b>SALEM</b> engineering group, inc.
PROPOSED STORAGE BUILDINGS S. SCHNOOR STREET MADERA, CALIFORNIA	DRAWN BY: VT	APPROVED BY: DL	
	PROJECT NO. 1-221-0369	FIGURE NO. 2	





## **APPENDIX A**

### **FIELD EXPLORATION**

Fieldwork for our investigation was conducted on April 15, 2021 and included a site visit, subsurface exploration, and soil sampling. The locations of the exploratory borings are shown on the Site Plan, Figure 1. Boring logs for our exploration are presented in figures following the text in this appendix. Borings were located in the field using existing reference points. Therefore, actual boring locations may deviate slightly.

The test borings were advanced with 6 5/8-inch diameter hollow flight auger rotated by a truck-mounted CME-45C drill rig. Visual classification of the materials encountered in the test borings was generally made in accordance with the Unified Soil Classification System (ASTM D2487).

Penetration resistance blow counts were obtained by dropping a 140-pound automated trip hammer through a 30-inch free fall to drive the sampler to a maximum penetration of 18 inches. The number of blows required to drive the last 12 inches, or less if very dense or hard, is recorded as Penetration Resistance (blows/foot) on the logs of borings. Soil samples were obtained from the test borings at the depths shown on the logs of borings. The MCS samples were recovered and capped at both ends to preserve the samples at their natural moisture content; SPT samples were recovered and placed in a sealed bag to preserve their natural moisture content. At the completion of drilling and sampling, the test borings were backfilled with drill cuttings, therefore, some settlement should be anticipated.



**SALEM**  
engineering group, inc.

**Test Boring: B-1**

**Page 1 Of: 2**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in.

**Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0							
260							
	5/6 6/6 5/6	CL-ML	Sandy Silty CLAY; very loose, light brown, damp, slight plasticity. Grades as above; stiff.	11	5.4	107.3	
5							
	10/6 11/6 10/6	SM	Silty SAND; medium dense, light brown, moist.	21	4.6	96.8	
255							
10							
	17/6 15/6 15/6		Grades as above; stiff, red to brown, [Hardpan].	30	13.0	--	
250							
15							
	3/6 7/6 6/6	SP-SM	Poorly Graded SAND with Silt; medium dense, light brown, moist, fine grained.	13	1.9	--	
245							
20							
	4/6 5/6 6/6		Grades as above; light brown to white, fine to medium grained.	11	2.8	--	
240							
25							
	8/6 13/6 14/6		Grades as above; medium dense, moist, red brown, with trace silt.	27	8.8	--	
235							

**Notes:**

**Figure Number A-1**



**SALEM**  
engineering group, inc.

**Project Number:** 1-221-0369

**Date:** 04/15/2021

**Test Boring:** B-1

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
30		CL	Sandy Lean CLAY; very stiff, red brown, moist, low plasticity.	20	24.8	--	
230			Grades as above.	30	10.7	--	
35			End of boring at 35ft. BSG				
225							
40							
220							
45							
215							
50							
210							
55							
205							
60							
200							

**Notes:**

**Figure Number A-1**





**SALEM**  
engineering group, inc.

**Test Boring: B-2**

**Page 1 Of: 1**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in. **Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0		CL-ML	Sandy Silty CLAY; stiff, light brown, damp, slight plasticity.	15	5.5	--	
260			Grades as above; firm.	9	6.2	92.1	
255			Grades as above; very stiff, light brown to brown, moist.	28	9.2	--	Low cementation.
250			Grades as above.	20	15.1	--	
15			End of boring at 15ft. BSG				
245							
20							
240							
25							
235							

**Notes:**

**Figure Number A-2**



**SALEM**  
engineering group, inc.

**Test Boring: B-3**

**Page 1 Of: 1**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in.

**Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0		CL-ML	Sandy Silty CLAY; stiff, light brown, damp, slight plasticity.				
260							
5			Grades as above; stiff.	20	11.5	90.4	
255							
10			Grades as above.	15	8.4	--	
250							
15			Grades as above; very stiff.	22	5.3	--	
245			End of boring at 16.5ft. BSG				
20							
240							
25							
235							

**Notes:**

**Figure Number A-3**



**SALEM**  
engineering group, inc.

**Test Boring: B-4**

**Page 1 Of: 1**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in.

**Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0		CL	Lean CLAY; stiff, light brown, damp, low plasticity.				
260	5/6 5/6 7/6			12	5.2	--	
5	7/6 9/6 12/6		Grades as above; very stiff.	21	6.2	97.6	
255							
10	4/6 8/6 10/6		Grades as above; red to brown, with pieces of cemented soil.	18	5.3	--	
250							
15	9/6 10/6 11/6	SM	Silty SAND; medium dense, light brown, moist, fine grained.	21	7.2	--	
245			End of boring at 16.5ft. BSG				
20							
240							
25							
235							

**Notes:**

**Figure Number A-4**



**SALEM**  
engineering group, inc.

**Test Boring: B-5**

**Page 1 Of: 1**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in.

**Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0		CL-ML	Sandy Silty CLAY; firm, light brown, damp, slight plasticity.				
260							
5			Grades as above.	6	7.2	--	
255							
10			Grades as above; very stiff, pieces of cemented soil.	18	12.3	--	
250							
15			Grades as above; hard, red to brown.	40	14.4	--	[Hardpan]
245			End of boring at 16.5ft. BSG				
20							
240							
25							
235							

**Notes:**

**Figure Number A-5**



**SALEM**  
engineering group, inc.

**Test Boring: B-6**

**Page 1 Of: 1**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in.

**Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0							
260							
5							
255							
10							
250							
15							
245							
20							
240							
25							
235							

**Notes:**

**Figure Number A-6**



**SALEM**  
engineering group, inc.

**Test Boring: B-7**

**Page 1 Of: 1**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in.

**Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0							
260							
5	5/6 9/6 12/6	SP-SM	Poorly Graded SAND with Silt; medium dense, brown to light brown, moist, fine grained.  Grades as above.	21	1.9	115.1	
255							
10	3/6 9/6 13/6	ML	Sandy SILT; very stiff, light brown, moist, slight plasticity, with pieces of hardpan.	22	10.8	--	
250							
15	7/6 13/6 20/6	SP-SM	Poorly Graded SAND with Silt; dense, light brown, moist, fine grained.	33	3.2	--	
245			End of boring at 15ft. BSG				
20							
240							
25							
235							

**Notes:**

**Figure Number A-7**



**SALEM**  
engineering group, inc.

**Test Boring: B-8**

**Page 1 Of: 1**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in.

**Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0		ML	Sandy SILT; very loose to stiff, damp, low plasticity.				
260	5/6 6/6 11/6	SP	Poorly Graded SAND; medium dense, brown, moist, fine grained.	17	3.4	111.3	
5	5/6 8/6 8/6	CL-ML	Sandy Silty CLAY; very stiff, light brown, moist, low plasticity.	16	8.0	--	
255							
10	8/6 11/6 10/6	SC	Clayey SAND; medium dense, damp, pieces of cemented soil.	21	4.3	--	
250							
15	10/6 12/6 13/6		Grades as above.	25	5.0	--	
245			End of boring at 16.5ft. BSG				
20							
240							
25							
235							

**Notes:**

**Figure Number A-8**



**SALEM**  
engineering group, inc.

**Test Boring: B-9**

**Page 1 Of: 1**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in.

**Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0		CL-ML	Sandy Silty CLAY; firm, brown, moist, fine grained.				
260			Grades as above.	7	4.0	--	
5							
255		SM	Silty SAND; medium dense, light brown, damp, slight plasticity.	18	9.0	--	
10			Grades as above.	20	5.3	--	
250							
15			End of boring at 15ft. BSG				
245							
20							
240							
25							
235							

**Notes:**

**Figure Number A-9**





**SALEM**  
engineering group, inc.

**Test Boring: B-10**

**Page 1 Of: 1**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in.

**Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0	2/6 3/6 2/6	SC-SM	Clayey Silty SAND; loose, light brown, damp, fine grained.	5	1.5	--	
260							
5	8/6 10/6 2/6	SC	Clayey SAND; medium dense, light brown, moist, Slight plasticity.	12	5.7	103.8	
255							
10	50/2		Grades as above; dense.	>50	5.8	87.8	
250							
15	7/6 7/6 10/6	SM	Silty SAND; medium dense, red to brown, fine grained.	17	5.8	--	
245							
20	11/6 18/6 17/6	ML	Sandy SILT; hard, red to brown, moist, low plasticity.	35	13.8	--	
240			End of boring at 21.5ft. due to density of soil.				
25							
235							

**Notes:**

**Figure Number A-10**



**SALEM**  
engineering group, inc.

**Test Boring: P-1**

**Page 1 Of: 1**

**Project Number: 1-221-0369**

**Date: 04/15/2021**

**Client: WHSE Partners**

**Project:** Proposed Storage Buildings

**Location:** S. Schnoor Street, Madera, CA.

**Drilled By:** Salem Engineering Group, Inc.

**Logged By:** RTM

**Drill Type:** CME 45C

**Elevation:** 262ft. AMSL

**Auger Type:** 6 5/8in. Hollow Stem Auger

**Initial Depth to Groundwater:** N/E

**Hammer Type:** Automatic Trip - 140lbs./30in.

**Final Depth to Groundwater:** N/E

ELEVATION/ DEPTH (feet)	SOIL SYMBOLS SAMPLER SYMBOLS AND FIELD TEST DATA	USCS	Soil Description	N-Values blows/ft.	Moisture Content %	Dry Density, PCF	Remarks
0		CL-ML	Sandy Silty CLAY; stiff, brown, moist, slight plasticity.	0	--	--	
260							
5							
255			Grades as above.				
10			End of boring at 8ft. BSG				
250							
15							
245							
20							
240							
25							
235							


**Notes:**


**Figure Number A-11**


# KEY TO SYMBOLS


## Symbol Description

### Strata symbols


 Silty low plasticity clay


 Silty sand


 Poorly graded sand with silt

 Lean Clay


 Silt

 Poorly graded sand

 Clayey sand


 Poorly graded clayey silty sand

### Misc. Symbols

 Boring continues

### Soil Samplers

 California sampler

 Standard penetration test

### Notes:

#### Granular Soils

Blows Per Foot (Uncorrected)

	MCS	SPT
Very loose	<5	<4
Loose	5-15	4-10
Medium dense	16-40	11-30
Dense	41-65	31-50
Very dense	>65	>50

#### Cohesive Soils

Blows Per Foot (Uncorrected)

	MCS	SPT
Very soft	<3	<2
Soft	3-5	2-4
Firm	6-10	5-8
Stiff	11-20	9-15
Very Stiff	21-40	16-30
Hard	>40	>30

MCS = Modified California Sampler

SPT = Standard Penetration Test Sampler

## Percolation Test Worksheet

**Project:** Proposed Storage Buildings  
Madera, CA.

**Job No.:** 1-221-0369

**Date Drilled:** 4/19/2021

**Soil Classification:**

Length of Pipe: 10.26 ft

Pipe stickup: 2.29 ft

Hole Dia.: 6.625 in.

Pipe Dia.: 3 in.

Gravel Below Pipe: 0.5 in.

Gravel pack porosity: 0.4

Gravel Correc Factor: 0.5

**Test Hole No.:** P-1

**Tested By:** RTM

**Presoaking Date:** 4/19/2021

**Test Date:** 4/19/2021

**Drilled Hole Depth:** 8.01 Feet

Time Start	Time Finish	Refill- Yes or No	Elapsed Time (hrs:min)	Initial Water Level# (ft)	Final Water Level# (ft)	Δ Water Level (in.)	Δ Min.	Uncorrected Percolation Rate (min/in)	Gravel Pack Corrected Unfactored Percolation Rate (min/in)	Estimated Unfactored Infiltration Rate (inches/hr)
7:24	7:29	N	0:05	8.25	8.30	0.60	5	8.3	15.9	0.2
7:29	7:39	N	0:10	8.30	8.39	1.08	10	9.3	17.7	0.2
7:39	7:59	N	0:20	8.39	8.49	1.20	20	16.7	31.9	0.1
7:59	8:19	N	0:20	8.49	8.59	1.20	20	16.7	31.9	0.1
8:19	8:49	N	0:30	8.59	8.70	1.32	30	22.7	43.5	0.1
8:49	9:19	N	0:30	8.70	8.76	0.72	30	41.7	79.7	0.1
9:19	9:49	N	0:30	8.76	8.84	0.96	30	31.3	59.7	0.1
9:49	10:19	N	0:30	8.84	8.90	0.72	30	41.7	79.7	0.1
10:19	10:49	N	0:30	8.90	8.98	0.96	30	31.3	59.7	0.1
<b>Estimated Unfactored Infiltration Rate (in/hr)</b>										0.1

APPENDIX

# B




## **APPENDIX B**

### **LABORATORY TESTING**

Laboratory tests were performed in accordance with generally accepted test methods of the American Society for Testing and Materials (ASTM), Caltrans, or other suggested procedures. Selected samples were tested for in-situ dry density and moisture content, corrosivity, consolidation, shear strength, expansion index, plasticity index, resistance value, and grain size distribution. The results of the laboratory tests are summarized in the following figures.

# CONSOLIDATION - PRESSURE TEST DATA ASTM D2435



Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369

Boring: B-1 @ 5'



## Direct Shear Test (ASTM D3080)

Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369

Client:

Boring: B-1 @ 2'

Soil Type: Sandy Silty CLAY (CL-MI)

Sample Type: Undisturbed Ring

Tested By: NL



Reviewed By:

Date of Test: 4/22/21

Test Equipment: GeoComp ShearTrac II

	Loading		
	1.0 kip	2.0 kip	3.0 kip
Normal Stress (ksf)	1.00	2.00	3.00
Shear Rate (in/min)	0.0040	0.0040	0.0040
Peak Shear Stress (ksf)	0.94	1.79	2.55

Initial Height of Sample (in)	1.000	1.000	1.000
Post-Consol. Sample Height (in.)	0.877	0.837	0.816
Post-Shear Sample Height (in.)	0.861	0.820	0.797
Diameter of Sample (in)	2.4	2.4	2.4
<b>Initial (pre-shear) Values</b>			
Moisture Content (%)	5.4		
Dry Density (pcf)	98.9	100.9	104.5
Saturation %	20.7	21.7	23.8
Void Ratio	0.70	0.67	0.61
Consolidated Void Ratio	0.49	0.39	0.31
<b>Final (post-shear) Values</b>			
Final Moisture Content (%)	25.4	23.2	20.3
Dry Density (pcf)	113.1	120.5	128.8
Saturation %	92.5	104.8	118.2
Void Ratio	0.74	0.60	0.46



Peak Shear Strength Values	
Slope	0.80
Friction Angle	39
Cohesion (psf)	153

## Direct Shear Test (ASTM D3080)

Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369

Client:

Boring: B-7 @ 3.5'

Soil Type: Poorly Graded SAND (SI)

Sample Type: Undisturbed Ring

Tested By: NL



Reviewed By:

Date of Test: 4/23/21

Test Equipment: GeoComp ShearTrac II

	Loading		
	1.0 kip	2.0 kip	3.0 kip
Normal Stress (ksf)	1.00	2.00	3.00
Shear Rate (in/min)	0.0040	0.0040	0.0040
Peak Shear Stress (ksf)	0.99	1.94	2.86


Initial Height of Sample (in)	1.000	1.000	1.000
Post-Consol. Sample Height (in.)	0.978	0.967	0.960
Post-Shear Sample Height (in.)	0.975	0.964	0.950
Diameter of Sample (in)	2.4	2.4	2.4
<b>Initial (pre-shear) Values</b>			
Moisture Content (%)	1.9		
Dry Density (pcf)	111.5	109.7	106.4
Saturation %	10.3	9.8	9.0
Void Ratio	0.50	0.52	0.57
Consolidated Void Ratio	0.46	0.47	0.50
<b>Final (post-shear) Values</b>			
Final Moisture Content (%)	17.7	18.0	17.8
Dry Density (pcf)	109.1	109.3	106.8
Saturation %	69.2	69.0	66.1
Void Ratio	0.68	0.70	0.72



Peak Shear Strength Values	
Slope	0.93
Friction Angle	43
Cohesion (psf)	61

# PARTICLE SIZE DISTRIBUTION DIAGRAM

## GRADATION TEST - ASTM C136



Percent Gravel	Percent Sand	Percent Silt/Clay
0%	47%	53%

Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	99.9%
#16	99.3%
#30	96.1%
#50	84.9%
#100	66.4%
#200	53.5%

Atterberg Limits		
PL=	LL=	PI=

Coefficients		
D85=	D60=	D50=
D30=	D15=	D10=
C <sub>u</sub> =	N/A	C <sub>c</sub> = N/A

USCS CLASSIFICATION
Sandy Silty CLAY (CL-ML)

Project Name: Proposed Storage Buildings - Madera, CA


Project Number: 1-221-0369

Boring: B-1 @ 2'



# PARTICLE SIZE DISTRIBUTION DIAGRAM

## GRADATION TEST - ASTM C136



Percent Gravel	Percent Sand	Percent Silt/Clay
0%	63%	37%

Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	99.8%
#16	98.4%
#30	94.6%
#50	82.4%
#100	55.1%
#200	36.7%

Atterberg Limits		
PL=	LL=	PI=

Coefficients		
D85=	D60=	D50=
D30=	D15=	D10=
C <sub>u</sub> =	N/A	C <sub>c</sub> = N/A

USCS CLASSIFICATION
Silty SAND (SM)

Project Name: Proposed Storage Buildings - Madera, CA


Project Number: 1-221-0369

Boring: B-1 @ 5'



# PARTICLE SIZE DISTRIBUTION DIAGRAM

## GRADATION TEST - ASTM C136



Percent Gravel	Percent Sand	Percent Silt/Clay
1%	94%	5%

Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	98.8%
#8	93.4%
#16	75.3%
#30	45.2%
#50	19.8%
#100	8.5%
#200	5.2%

Atterberg Limits		
PL=	LL=	PI=

Coefficients		
D85=	D60=	D50=
D30=	D15=	D10=
C <sub>u</sub> =	N/A	C <sub>c</sub> = N/A

USCS CLASSIFICATION
Poorly Graded SAND (SP)

Project Name: Proposed Storage Buildings - Madera, CA


Project Number: 1-221-0369

Boring: B-1 @ 15'



# PARTICLE SIZE DISTRIBUTION DIAGRAM

## GRADATION TEST - ASTM C136



Percent Gravel	Percent Sand	Percent Silt/Clay
0%	80%	20%

Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	98.0%
#16	86.7%
#30	57.8%
#50	32.0%
#100	23.1%
#200	19.6%

Atterberg Limits		
PL=	LL=	PI=

Coefficients		
D85=	D60=	D50=
D30=	D15=	D10=
C <sub>u</sub> =	N/A	C <sub>c</sub> = N/A

USCS CLASSIFICATION
Poorly Graded SAND(SP-SM)

Project Name: Proposed Storage Buildings - Madera, CA


Project Number: 1-221-0369

Boring: B-1 @ 25'



# PARTICLE SIZE DISTRIBUTION DIAGRAM

## GRADATION TEST - ASTM C136



Percent Gravel	Percent Sand	Percent Silt/Clay
0%	43%	57%

Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	99.4%
#16	97.2%
#30	90.6%
#50	80.0%
#100	68.4%
#200	57.1%

Atterberg Limits		
PL=	LL=	PI=

Coefficients		
D85=	D60=	D50=
D30=	D15=	D10=
C <sub>u</sub> =	N/A	C <sub>c</sub> = N/A

USCS CLASSIFICATION
Sandy Silty CLAY (CL-ML)

Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369


Boring: B-2 @ 8.5'





# PARTICLE SIZE DISTRIBUTION DIAGRAM

## GRADATION TEST - ASTM C136



Percent Gravel	Percent Sand	Percent Silt/Clay
0%	35%	65%

Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	99.5%
#8	97.8%
#16	94.8%
#30	89.9%
#50	83.0%
#100	73.2%
#200	65.1%

Atterberg Limits		
PL=	LL=	PI=

Coefficients		
D85=	D60=	D50=
D30=	D15=	D10=
C <sub>u</sub> =	N/A	C <sub>c</sub> = N/A

USCS CLASSIFICATION
Sandy Silty CLAY (CL-ML)

Project Name: Proposed Storage Buildings - Madera, CA


Project Number: 1-221-0369

Boring: B-3 @ 5'



## PARTICLE SIZE DISTRIBUTION DIAGRAM

### GRADATION TEST - ASTM C136



Percent Gravel	Percent Sand	Percent Silt/Clay
0%	42%	58%

Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	99.7%
#8	97.7%
#16	96.3%
#30	94.8%
#50	90.5%
#100	74.2%
#200	58.1%

Atterberg Limits		
PL=	LL=	PI=

Coefficients		
D85=	D60=	D50=
D30=	D15=	D10=
C <sub>u</sub> =	N/A	C <sub>c</sub> = N/A

USCS CLASSIFICATION
Sandy Lean CLAY (CL)

**Project Name: Proposed Storage Buildings - Madera, CA**


**Project Number: 1-221-0369**

**Boring: B-4 @ 10'**



# PARTICLE SIZE DISTRIBUTION DIAGRAM

## GRADATION TEST - ASTM C136



Percent Gravel	Percent Sand	Percent Silt/Clay
0%	88%	12%

Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	99.6%
#8	94.8%
#16	81.9%
#30	58.2%
#50	35.6%
#100	18.6%
#200	11.6%

Atterberg Limits		
PL=	LL=	PI=

Coefficients		
D85=	D60=	D50=
D30=	D15=	D10=
C <sub>u</sub> =	N/A	C <sub>c</sub> = N/A

USCS CLASSIFICATION
Poorly Graded SAND (SP-SM)

Project Name: Proposed Storage Buildings - Madera, CA


Project Number: 1-221-0369

Boring: B-7 @ 3.5'



# PARTICLE SIZE DISTRIBUTION DIAGRAM

## GRADATION TEST - ASTM C136



Percent Gravel	Percent Sand	Percent Silt/Clay
0%	72%	28%

Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	99.6%
#16	96.9%
#30	88.9%
#50	66.9%
#100	40.8%
#200	27.8%

Atterberg Limits		
PL=	LL=	PI=

Coefficients		
D85=	D60=	D50=
D30=	D15=	D10=
C <sub>u</sub> =	N/A	C <sub>c</sub> = N/A

USCS CLASSIFICATION
Clayey SAND (SC)

Project Name: Proposed Storage Buildings - Madera, CA


Project Number: 1-221-0369

Boring: B-8 @ 10'



# PARTICLE SIZE DISTRIBUTION DIAGRAM

## GRADATION TEST - ASTM C136



Percent Gravel	Percent Sand	Percent Silt/Clay
0%	54%	46%

Sieve Size	Percent Passing
3/4 inch	100.0%
1/2 inch	100.0%
3/8 inch	100.0%
#4	100.0%
#8	99.3%
#16	96.6%
#30	90.1%
#50	80.3%
#100	63.7%
#200	45.9%

Atterberg Limits		
PL=	LL=	PI=

Coefficients		
D85=	D60=	D50=
D30=	D15=	D10=
C <sub>u</sub> =	N/A	C <sub>c</sub> = N/A

USCS CLASSIFICATION
Clayey SAND (SC)

Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369

Boring: B-10 @ 5'



# Atterberg Limits Determination

## ASTM D4318

Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369

Date Sampled: 4/15/21

Date Tested: 4/19/21

Sampled By: SEG

Tested By: KN

Sample Location: B-1 @ 2'


Run Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare	28.08	28.82	29.49	32.11	30.77	31.97
Weight of Dry Soil & Tare	26.96	27.64	28.22	30.13	29.04	29.77
Weight of Water	1.12	1.18	1.27	1.98	1.73	2.20
Weight of Tare	20.63	21.02	20.95	20.91	21.07	20.30
Weight of Dry Soil	6.33	6.62	7.27	9.22	7.97	9.47
Water Content	17.7	17.8	17.5	21.5	21.7	23.2
Number of Blows				30	25	16

Plastic Limit : 18

Liquid Limit : 22

Plasticity Index : 4

Unified Soil Classification : CL/ML



## Atterberg Limits Determination

### ASTM D4318

Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369

Date Sampled: 4/15/21

Date Tested: 4/20/21

Sampled By: SEG

Tested By: IM

Sample Location: B-1 @ 5'


Run Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare	28.88	29.16	29.29	29.68	31.61	33.72
Weight of Dry Soil & Tare	27.37	27.61	27.76	27.86	29.41	30.83
Weight of Water	1.51	1.55	1.53	1.82	2.20	2.89
Weight of Tare	20.98	20.87	21.10	20.43	21.18	20.47
Weight of Dry Soil	6.39	6.74	6.66	7.43	8.23	10.36
Water Content	23.6	23.0	23.0	24.5	26.7	27.9
Number of Blows				29	20	17

Plastic Limit : 23

Liquid Limit : 26

Plasticity Index : 3

Unified Soil Classification : OL/ML





# Atterberg Limits Determination

## ASTM D4318

Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369

Date Sampled: 4/15/21

Date Tested: 4/20/21

Sampled By: SEG

Tested By: IM

Sample Location: B-4 @ 10'


Run Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare	27.94	27.78	27.72	35.98	32.84	31.43
Weight of Dry Soil & Tare	27.04	26.83	26.79	33.25	30.55	29.34
Weight of Water	0.90	0.95	0.93	2.73	2.29	2.09
Weight of Tare	20.98	20.44	20.54	21.07	20.90	20.60
Weight of Dry Soil	6.06	6.39	6.25	12.18	9.65	8.74
Water Content	14.9	14.9	14.9	22.4	23.7	23.9
Number of Blows				32	23	19

Plastic Limit : 15

Liquid Limit : 23

Plasticity Index : 8

Unified Soil Classification : CL



# EXPANSION INDEX TEST

## ASTM D4829

Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369

Date Sampled: 4/15/21

Date Tested: 4/20/21

Sampled By: SEG

Tested By: IM

Sample Location: B-1 @ 0 - 5'

Soil Description: Silty SAND (SM)

Trial #	1	2	3
Weight of Soil & Mold, g.	587.0		
Weight of Mold, g.	187.8		
Weight of Soil, g.	399.2		
Wet Density, pcf	120.4		
Weight of Moisture Sample (Wet), g.	845.0		
Weight of Moisture Sample (Dry), g.	771.5		
Moisture Content, %	9.5		
Dry Density, pcf	109.9		
Specific Gravity of Soil	2.7		
Degree of Saturation, %	48.3		

Time	Initial	30 min	1 hr	6 hrs	12 hrs	24 hrs
Dial Reading	0	0.0173	0.019	--	--	0.0207

Expansion Index<sub>measured</sub> = 20.7

Expansion Index<sub>50</sub> = 19.8

**Expansion Index =**

**20**

Expansion Potential Table	
Exp. Index	Potential Exp.
0 - 20	Very Low
21 - 50	Low
51 - 90	Medium
91 - 130	High
>130	Very High

# Resistance R-Value and Expansion Pressure of Compacted Soils ASTM D2844

Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369

Date Sampled: 4/15/21


Date Tested: 4/23/21

Sampled By: SEG

Tested By: MZ

Sample Location: B-1 @ 0 - 5'

Soil Description: Silty SAND (SM)



Specimen	1	2	3
Exudation Pressure, psi	497.6	339.5	187.2
Moisture at Test, %	10.6	11.0	11.6
Dry Density, pcf	122.2	121.7	120.1
Expansion Pressure, psf	307	273	134
Thickness by Stabilometer, in.	2.6	3.5	4.4
Thickness by Expansion Pressure, in.	2.8	2.5	1.2
R-Value by Stabilometer	74	65	56
R-Value by Expansion Pressure	N/A		
R-Value at 300 psi Exudation Pressure	62.5		

<b>Controlling R-Value</b>	<b>63</b>
----------------------------	-----------

## CHEMICAL ANALYSIS

### SO<sub>4</sub> - Modified CTM 417 & Cl - Modified CTM 417/422

Project Name: Proposed Storage Buildings - Madera, CA

Project Number: 1-221-0369

Date Sampled: 4/15/21

Date Tested: 4/21/21

Sampled By: SEG

Tested By: NS

Soil Description: Silty SAND (SM)

Sample Number	Sample Location	Soluble Sulfate SO <sub>4</sub> -S	Soluble Chloride Cl	pH
1a.	B-1 @ 0 - 5'	< 50 mg/kg	26 mg/kg	8.0
1b.	B-1 @ 0 - 5'	< 50 mg/kg	27 mg/kg	8.0
1c.	B-1 @ 0 - 5'	< 50 mg/kg	28 mg/kg	8.0
<b>Average:</b>		<b>&lt; 50 mg/kg</b>	<b>27 mg/kg</b>	<b>8.0</b>

# SOIL RESISTIVITY


## CTM 643

Project Name: Proposed Storage Buildings - Madera Date Sampled: 4/15/21  
 Project Number: 1-221-0369 Sampled By: SEG  
 Sample Location: B-1 @ 0 - 5' Date Tested: 4/23/21  
 Soil Description: Silty SAND (SM) Tested By: KN

Chloride Content: 27 mg/Kg Initial Sample Weight: 700 gms  
 Sulfate Content: < 50 mg/Kg Test Box Constant: 1.010 cm  
 Soil pH: 8.0

### Test Data:

Trial #	Water Added (mL)	Meter Dial Reading	Multiplier Setting	Resistance (ohms)	Resistivity (ohm-cm)
1	100	8.5	1,000	8,500	8,585
2	150	6.8	1,000	6,800	6,868
3	200	8.4	1,000	8,400	8,484



Minimum Resistivity:	<b>6,882</b> ohm-cm
----------------------	---------------------

APPENDIX

C



## APPENDIX C

### GENERAL EARTHWORK AND PAVEMENT SPECIFICATIONS

When the text of the report conflicts with the general specifications in this appendix, the recommendations in the report have precedence.

**1.0 SCOPE OF WORK:** These specifications and applicable plans pertain to and include all earthwork associated with the site rough grading, including, but not limited to, the furnishing of all labor, tools and equipment necessary for site clearing and grubbing, stripping, preparation of foundation materials for receiving fill, excavation, processing, placement and compaction of fill and backfill materials to the lines and grades shown on the project grading plans and disposal of excess materials.

**2.0 PERFORMANCE:** The Contractor shall be responsible for the satisfactory completion of all earthwork in accordance with the project plans and specifications. This work shall be inspected and tested by a representative of SALEM Engineering Group, Incorporated, hereinafter referred to as the Soils Engineer and/or Testing Agency. Attainment of design grades, when achieved, shall be certified by the project Civil Engineer. Both the Soils Engineer and the Civil Engineer are the Owner's representatives. If the Contractor should fail to meet the technical or design requirements embodied in this document and on the applicable plans, he shall make the necessary adjustments until all work is deemed satisfactory as determined by both the Soils Engineer and the Civil Engineer. No deviation from these specifications shall be made except upon written approval of the Soils Engineer, Civil Engineer, or project Architect.

No earthwork shall be performed without the physical presence or approval of the Soils Engineer. The Contractor shall notify the Soils Engineer at least 2 working days prior to the commencement of any aspect of the site earthwork.

The Contractor shall assume sole and complete responsibility for job site conditions during the course of construction of this project, including safety of all persons and property; that this requirement shall apply continuously and not be limited to normal working hours; and that the Contractor shall defend, indemnify and hold the Owner and the Engineers harmless from any and all liability, real or alleged, in connection with the performance of work on this project, except for liability arising from the sole negligence of the Owner or the Engineers.

**3.0 TECHNICAL REQUIREMENTS:** All compacted materials shall be densified to no less than 92 percent of relative compaction (based on ASTM D1557 Test Method (latest edition), or as specified in the technical portion of the Soil Engineer's report. The location and frequency of field density tests shall be determined by the Soils Engineer. The results of these tests and compliance with these specifications shall be the basis upon which satisfactory completion of work will be judged by the Soils Engineer.

**4.0 SOILS AND FOUNDATION CONDITIONS:** The Contractor is presumed to have visited the site and to have familiarized himself with existing site conditions and the contents of the data presented in the Geotechnical Engineering Report. The Contractor shall make his own interpretation of the data contained in the Geotechnical Engineering Report and the Contractor shall not be relieved of liability for any loss sustained as a result of any variance between conditions indicated by or deduced from said report and the actual conditions encountered during the progress of the work.



**5.0 DUST CONTROL:** The work includes dust control as required for the alleviation or prevention of any dust nuisance on or about the site or the borrow area, or off-site if caused by the Contractor's operation either during the performance of the earthwork or resulting from the conditions in which the Contractor leaves the site. The Contractor shall assume all liability, including court costs of codefendants, for all claims related to dust or wind-blown materials attributable to his work. Site preparation shall consist of site clearing and grubbing and preparation of foundation materials for receiving fill.

**6.0 CLEARING AND GRUBBING:** The Contractor shall accept the site in this present condition and shall demolish and/or remove from the area of designated project earthwork all structures, both surface and subsurface, trees, brush, roots, debris, organic matter and all other matter determined by the Soils Engineer to be deleterious. Such materials shall become the property of the Contractor and shall be removed from the site.

Tree root systems in proposed improvement areas should be removed to a minimum depth of 3 feet and to such an extent which would permit removal of all roots greater than 1 inch in diameter. Tree roots removed in parking areas may be limited to the upper 1½ feet of the ground surface. Backfill of tree root excavations is not permitted until all exposed surfaces have been inspected and the Soils Engineer is present for the proper control of backfill placement and compaction. Burning in areas which are to receive fill materials shall not be permitted.

**7.0 SUBGRADE PREPARATION:** Surfaces to receive Engineered Fill and/or building or slab loads shall be prepared as outlined above, scarified to a minimum of 12 inches, moisture-conditioned as necessary, and compacted to 92 percent relative compaction.

Loose soil areas and/or areas of disturbed soil shall be moisture-conditioned as necessary and compacted to 92 percent relative compaction. All ruts, hummocks, or other uneven surface features shall be removed by surface grading prior to placement of any fill materials. All areas which are to receive fill materials shall be approved by the Soils Engineer prior to the placement of any fill material.

**8.0 EXCAVATION:** All excavation shall be accomplished to the tolerance normally defined by the Civil Engineer as shown on the project grading plans. All over-excavation below the grades specified shall be backfilled at the Contractor's expense and shall be compacted in accordance with the applicable technical requirements.

**9.0 FILL AND BACKFILL MATERIAL:** No material shall be moved or compacted without the presence or approval of the Soils Engineer. Material from the required site excavation may be utilized for construction site fills, provided prior approval is given by the Soils Engineer. All materials utilized for constructing site fills shall be free from vegetation or other deleterious matter as determined by the Soils Engineer.

**10.0 PLACEMENT, SPREADING AND COMPACTION:** The placement and spreading of approved fill materials and the processing and compaction of approved fill and native materials shall be the responsibility of the Contractor. Compaction of fill materials by flooding, ponding, or jetting shall not be permitted unless specifically approved by local code, as well as the Soils Engineer. Both cut and fill shall be surface-compacted to the satisfaction of the Soils Engineer prior to final acceptance.

**11.0 SEASONAL LIMITS:** No fill material shall be placed, spread, or rolled while it is frozen or thawing, or during unfavorable wet weather conditions. When the work is interrupted by heavy rains, fill

operations shall not be resumed until the Soils Engineer indicates that the moisture content and density of previously placed fill is as specified.

**12.0 DEFINITIONS** - The term "pavement" shall include asphaltic concrete surfacing, untreated aggregate base, and aggregate subbase. The term "subgrade" is that portion of the area on which surfacing, base, or subbase is to be placed.

The term "Standard Specifications": hereinafter referred to, is the most recent edition of the Standard Specifications of the State of California, Department of Transportation. The term "relative compaction" refers to the field density expressed as a percentage of the maximum laboratory density as determined by ASTM D1557 Test Method (latest edition).

**13.0 PREPARATION OF THE SUBGRADE** - The Contractor shall prepare the surface of the various subgrades receiving subsequent pavement courses to the lines, grades, and dimensions given on the plans. The upper 12 inches of the soil subgrade beneath the pavement section shall be compacted to a minimum relative compaction of 95 percent based upon ASTM D1557. The finished subgrades shall be tested and approved by the Soils Engineer prior to the placement of additional pavement courses.

**14.0 AGGREGATE BASE** - The aggregate base material shall be spread and compacted on the prepared subgrade in conformity with the lines, grades, and dimensions shown on the plans. The aggregate base material shall conform to the requirements of Section 26 of the Standard Specifications for Class 2 material, ¾-inch or 1½-inches maximum size. The aggregate base material shall be compacted to a minimum relative compaction of 95 percent based upon ASTM D1557. The aggregate base material shall be spread in layers not exceeding 6 inches and each layer of aggregate material course shall be tested and approved by the Soils Engineer prior to the placement of successive layers.

**15.0 AGGREGATE SUBBASE** - The aggregate subbase shall be spread and compacted on the prepared subgrade in conformity with the lines, grades, and dimensions shown on the plans. The aggregate subbase material shall conform to the requirements of Section 25 of the Standard Specifications for Class 2 Subbase material. The aggregate subbase material shall be compacted to a minimum relative compaction of 95 percent based on ASTM D1557, and it shall be spread and compacted in accordance with the Standard Specifications. Each layer of aggregate subbase shall be tested and approved by the Soils Engineer prior to the placement of successive layers.

**16.0 ASPHALTIC CONCRETE SURFACING** - Asphaltic concrete surfacing shall consist of a mixture of mineral aggregate and paving grade asphalt, mixed at a central mixing plant and spread and compacted on a prepared base in conformity with the lines, grades, and dimensions shown on the plans. The viscosity grade of the asphalt shall be PG 64-10, unless otherwise stipulated or local conditions warrant more stringent grade. The mineral aggregate shall be Type A or B, ½ inch maximum size, medium grading, and shall conform to the requirements set forth in Section 39 of the Standard Specifications. The drying, proportioning, and mixing of the materials shall conform to Section 39. The prime coat, spreading and compacting equipment, and spreading and compacting the mixture shall conform to the applicable chapters of Section 39, with the exception that no surface course shall be placed when the atmospheric temperature is below 50 degrees F. The surfacing shall be rolled with a combination steel-wheel and pneumatic rollers, as described in the Standard Specifications. The surface course shall be placed with an approved self-propelled mechanical spreading and finishing machine.